

FLOOR PLAN DETAIL

NOTES:-

- All dimensions are in m, unless wherever specified diameter of the bars shown in mm
- Dimensions are not to be scaled out, only written dimensions may be taken as correct.
- Nominal mix concrete 1:1.5:3 according IS 456 Clause 9.3
- The reinforcement shall be of high strength deformed steel bars conforming to IS:1786-2008
- Lap length and development length (L_d) for 8 mm Φ is 400 mm
- Second class brick must be used
- Mortar 1:5 according to Table 3 IS 4326-2013
- All walls are one Brick Thick Masonry walls or Autoclaved Aerated Block of Class 7.5
- Any discrepancy in the structural drawings should be correlated with architectural drawing.
- Refer DWG-2 to DWG-5 for earthquake resistance and structural detail.

Schedule of Door & Windows

Name	Lintel	Width	Sill W	Description
D1	2.10	0.90	--	
D2	2.10	0.75	--	
W1	2.10	1.50	0.90	
W2	2.10	1.20	0.90	
W3	2.10	0.90	0.90	
V	2.10	0.60	1.80	

NOTES:-

Clear height of DU = 2.85 m
 Earthquake resistance structure as per site condition
 * All the Dimensions in m

DRG. No. - NIT/CED/2017/PMAY-OP3-RCC-SR-Z-V/DWG-1

NATIONAL INSTITUTE OF TECHNOLOGY HAMIRPUR


BUILDING NAME:
 PMAY HFA
 OPTION 3
 RCC BUILDING
 SLOPING ROOF
 ZONE V

DRAWING TITLE:
 FLOOR PLAN

DESIGNED BY:
 Dr. Pardeep Kumar
 Dr. Hemant Kumar Vinayak

Hemant
Dr. Hemant Kumar Vinayak
 Assistant Professor
 Department of Civil Engineering
 National Institute of Technology,
 Hamirpur -177005 (H.P.)

Pardeep
Dr. Pardeep Kumar
 Associate Professor (Structural Engg.)
 Civil Engineering Department
 NIT, Hamirpur (H.P.)-177005

Sl. No.	Column	Transverse reinforcement	Sectional plan with longitudinal reinf. Footing top/roof level
1.	C1	8Ø @100mm C/C *A* 8Ø @150mm C/C *B*	

All Column Size are 35cm x 35cm and Grade is M20







CHART SHOWING DETAIL OF ISOLATED FOOTING REINFORCEMENT

Sr. No.	Name of footing	Size of column (bxd)	Size of footing (BXD)	Size of pit (B1XD1)	Thickness of footing T2	d-eff.	h	Spacing of reinf. parallel to x-x	Spacing of reinf. parallel to y-y
1.	F1	35 X 35	120 X 120	130 X 130	30	25	20	8Ø @ 200mm C/C	8Ø @ 200mm C/C



NOTES:-

- All dimensions are in cm unless wherever specified diameter of the Bars shown in mm.
- Dimensions are not to be scaled out, only written dimensions may be taken as correct.
- Safe bearing capacity for design of footing is considered at 15 T/m² to be ensured at site.
- Grade of concrete M:20.
- The reinforcement shall be of high strength deformed steel bars conforming to IS:1786-2008.
- Minimum clear cover to the reinforcement including stirrups:-
 - (i) Beam 25 mm
 - (ii) Column 40 mm
 - (iii) Footing 50 mm
- Lap length and development length (L_d)
 - (i) For 16 mm Ø = 800
 - (ii) For 12 mm Ø = 600
 - (iii) for 8 mm Ø = 400
- The concrete shall be mechanically mixed and vibrated with water-cement ratio not exceeding 0.55.
- Incase the proposed building is at probable landslide prone area the soil should be retained properly with adequate retaining wall to prevent differential settlement of the foundation.
- Any discrepancy in the structural drawing should be correlated with architectural drawing

DRG. No. - NIT/CEED/2017/OP-3-RCC-SR
 Z-V/WG-2

NATIONAL INSTITUTE OF
 TECHNOLOGY HAMIRPUR

BUILDING NAME :
 PMAY HFA
 OPTION 3
 RCC BUILDING
 SLOPING ROOF
 ZONE V

DETAIL OF FOOTINGS & COLUMN



DESIGNED BY:
 Dr. Pardeep Kumar
 Dr. Hemant Kumar Vinayak

Hemant Kumar Vinayak
Dr. Hemant Kumar Vinayak
 Assistant Professor
 Department of Civil Engineering
 National Institute of Technology,
 Hamirpur -177005 (H.P.)


Pardeep Kumar
Dr. Pardeep Kumar
 Associate Professor (Structural Engg.)
 Civil Engineering Department
 NIT, Hamirpur (H.P.)-177005

DETAILED DRAWING OF REINFORCEMENT OF BEAMS AT PLINTH/ROOF LEVEL

S - 8 mm dia bars @ 100 mm c/c



DETAIL FOR BEAM PB/RB-1 to PB/RB-6



DETAIL FOR BEAM PB/RB-7 to PB/RB-12

NOTES :

- All dimensions are in meters, unless wherever specified diameter of the bars shown in mm.
- Dimensions are not to be scaled out, only written dimensions may be taken as correct.
- Size of Beam is 250 X 250 mm.
- Grade of concrete shall be M20.
- All reinforcement shall be of grade Fe 415 confirming to IS:1786-2008.
- Clear Cover to reinforcement shall be 25 mm.
- Bending and fixing of reinforcement shall be as per IS:2502-1963.
- Lap length and anchorage length shall be 57 times the bar diameter
- Further refer notes from the drawing of 'Detail' of footings'.

DRG. No. - NIT/CED/2017/OP-3-RCC-SR Z-V/DWG-3

**NATIONAL INSTITUTE OF
TECHNOLOGY HAMIRPUR**

**BUILDING NAME :
PMAY HFA
OPTION 3
RCC BUILDING
SLOPING ROOF
ZONE V**

DETAIL OF PLINTH /ROOF BEAM


**DESIGNED BY:
Dr. Pardeep Kumar
Dr. Hemant Kumar Vinayak**

Hemant Vinayak
Dr. Hemant Kumar Vinayak
Assistant Professor
Department of Civil Engineering
National Institute of Technology,
Hamirpur -177005 (H.P.)

Pardeep Kumar
Dr. Pardeep Kumar
Associate Professor (Structural Engg.)
Civil Engineering Department
NIT, Hamirpur (H.P.)-177005

NOTES:-

- All dimensions are in mm unless specified.
- Dimensions are not to be scaled out, only written dimensions may be taken as correct.
- Grade of concrete M:20.
- Any discrepancy in structural Drawings should be correlated with Architectural drawing.
- Scale : Not to scale
- Truss has been designed for 0.3m snow depth.



ANGLE SIZE	WELD THK W, mm	a(mm)	b(mm)	GUSSET THK mm
L-50 x 50 x 5	6	50	90	8

TYPICAL DETAILS OF WELD LENGTH


DRG. No. - NIT/CED/2017/PMAY -OP3-RCC-SR-Z-V/DWG-5

NATIONAL INSTITUTE OF TECHNOLOGY HAMIRPUR


BUILDING NAME:
PMAY HFA
OPTION 3
REINFORCED CONCRETE
BUILDING
SLOPING ROOF
ZONE V

DRAWING TITLE:
CROSS SECTION OF TRUSS


DESIGNED BY:
Dr. Pardeep Kumar
Dr. Hemant Kumar Vinayak



Elevation Detail 3




Plan Detail 3



Plan Detail 4

Detail 2



Detail 1

Dr. Pardeep Kumar
 Associate Professor (Structural Engg.)
 Civil Engineering Department
 NIT, Hamirpur (H.P.)-177005

Dr. Hemant Kumar Vinayak
 Assistant Professor
 Department of Civil Engineering
 National Institute of Technology,
 Hamirpur -177005 (H.P.)